


EDCON-COMPONENTS




Specifications

Insulation Material: Polyvinyl Chloride (PVC)
 Conductor: #28 AWG (7*0,127) Stranded Tinned Coppe
 UL-Style: 2651
 Colour of Isolation: Gray w. Red Line
 Operating Temperature: -20°C to +105°C
 Flammability Rating: UL-VW-1
 Voltage Rating: 300V

Electrical:
 Impedance: 120Ω (Unbalanced)
 Capacitance: 11,2pf/feet
 Inductance: 14μH/Feet
 Insulation Resistance: 1GΩ / M min.

Dimensions (mm)


Pos.	A	B
4	11,16	10,00
5	13,70	12,50
6	16,24	15,00
7	18,78	17,50
8	21,32	20,00
9	23,86	22,50
10	26,40	25,00
11	28,94	27,50
12	31,48	30,00
13	34,02	32,50
14	36,56	35,00
15	39,10	37,50
16	41,64	40,00
17	44,18	42,50
18	46,72	45,00
19	49,26	47,50
20	51,80	50,00
21	54,34	52,50
22	56,88	55,00
23	59,42	57,50
24	61,96	60,00



Flat Ribbon Cable Pitch 2,54mm AWG28	
Part No.:	T29039
Customer:	

DRW:	Jason	CHKD	Wilson	MATL:	Wilson	TOLERANCE	Mason	DATE	13.12.2018
APPD:	Schumi			FINISH	Jamy		Sheet No.		1 from 2

EDCON-COMPONENTS



Ordering Informations

Serie	Number of Position	Colour of Cable	AWG Size	Special function	Special function	ROHS	Packing
T29039	xx	GY	28	00	00	R	Rxx

xx= Like Table	GY= Gray	28= wire Size AWG28	00= No function	00= No function	R= ROHS Conform N= NON ROHS Conform	Rxx= Length of cable per Reel

Flat Ribbon Cable Pitch 2,54mm AWG28	
Part No.:	T29039
Customer:	

DRW:	Jason	CHKD	Wilson	MATL:	Wilson	TOLERANCE	Mason	DATE	13.12.2018
APPD:	Schumi			FINISH	Jamy		Sheet No.		2 from 2