


# EDCON-COMPONENTS




## Specifications

Insulation Material: Polyvinyl Chloride (PVC)  
 Conductor: #24 AWG (7\*0,203) Stranded Tinned Coppe  
 UL-Style: 2651  
 Colour of Isolation: Gray w. Red Line  
 Operating Temperature: -20°C to +105°C  
 Flammability Rating: UL-VW-1  
 Voltage Rating: 300V

Electrical:  
 Impedance: 96Ω ( Unbalanced)  
 Capacitance: 14,6pf/feet  
 Inductance: 14μH/Feet  
 Insulation Resistance: 1GΩ / M min.

## Dimensions (mm)

Pos.	A	B
10	17,30	15,90
20	33,20	31,80
30	49,10	47,70
40	65,00	63,60
50	80,90	79,50




**Flat Ribbon Cable Pitch  
1,59mm AWG24**

Part No.: **T29041**

DRW:	Jason	CHKD	Wilson	MATL:	Wilson	TOLERANCE	Mason	DATE	13.12.2018	Customer:
APPD:	Schumi			FINISH	Jamy		Sheet No.	1 from 2		

# EDCON-COMPONENTS



## Ordering Informations

Serie	Number of Position	Colour of Cable	AWG Size	Special function	Special function	ROHS	Packing
<b>T29041</b>	<b>xx</b>	<b>GY</b>	<b>24</b>	<b>00</b>	<b>00</b>	<b>R</b>	<b>Rxx</b>

xx= Like Table	GY= Gray	24= wire Size AWG24	00= No function	00= No function	R= ROHS Conform N= NON ROHS Conform	Rxx= Length of cable per Reel

**Flat Ribbon Cable Pitch  
1,59mm AWG24**  
Part No.: **T29041**  
Customer:

DRW:	Jason	CHKD	Wilson	MATL:	Wilson	TOLERANCE	Mason	DATE	13.12.2018
APPD:	Schumi			FINISH	Jamy		Sheet No.		2 from 2