



EDCON-COMPONENTS



Technical Information

Style	UL2651
Pitch	3,96mm
AWG Size Available:	28, 26, 24, 22, 20
Construction	21/0.178mm ±0,008
Conductor Wire	Tinned Copper
Conductor Diameter:	0,95mm ± 0,05
Minimum Thickness:	0,30mm
Maximum Thickness:	0,38mm
Colour:	Gray
Diameter:	1,70mm ± 0,05
Temperatur Material:	105°C
Rating:	300V
Temperatur Range:	.-20°C to + 105°C
Dielectric withstand.	2500V AC/minute
Spark Test	3000V 0.15Sec Min
Conductor Resistance:	Max. 34,9Ω/KM 20°C
Insulation Resistance:	Min 0,75MΩ/KM 20°C

Technical Drawing




**FLAT CABLE Gray Pitch
3,96mm**

Part No.: **T29004**

DRW:	Jason	CHKD	Wilson	MATL:	Wilson	TOLERANCE	Mason	DATE	04.07.2018
APPD:	Schumi			FINISH	Jamy		Sheet No.	1 from 2	

Customer:

EDCON-COMPONENTS



Ordering Informations

Serie	No of Cores	Cable Color	AWG Size	Meter/Reel
-------	-------------	-------------	----------	------------

T29004	xx	GR	20	61
---------------	-----------	-----------	-----------	-----------

xx= 2~68Pos.	GR= Gray w. RED-Line	XX= Look Description	
			61= 61 Meter/Reel

FLAT CABLE Gray Pitch 3,96mm
Part No.: T29004
Customer:

DRW:	Jason	CHKD	Wilson	MATL:	Wilson	TOLERANCE	Mason	DATE	04.07.2018
APPD:	Schumi			FINISH	Jamy		Sheet No.	2 from 2	

www.edcon-components.com

email: info@edcon-components.com